



ELECTRICAL SAFETY TESTING/ CALIBRATION				
Report No : HBMS/CAL/23-24		Calibration Date : 28.09.2023		
		Calibration Valid : 27.03.2024		
1.1CUSTO	MER DETAILS:			
Name and Address of the organization		M/S, PRIMARY HEALTH CENTRE,		
		CHITHALANDUR, NAMAKKAL.		
<b>1.2. DESC</b>	RIPTION OF DEVICE UNDER TEST	Γ (DUT):		
EQUIPME	ENT NAME	MICROSCOPE		
i	Manufactured by	OLYMPUS		
ii	Model	CH20I		
iii	Serial No	8F03739		
iv	Location	LABORATORY		
l		I. J		

2.CONDITION OF THE ITEM WHEN RECEIVED	
No visible damages and in working order	

3.TEST DONE	Electrical safety/ Performance Testing

4. STATUS						
Manufactures Specification	User specification	Within specification	Out of specification	Calibration	Electrical Safety Test	Performance Analysis
V	-	$\checkmark$	-	-		-

9			
•			

 $\bowtie$ 

No. 42/1, Navaindia Road, Peelamedu,

99400 28355, 97512 06106

hbmedicalsystem@gmail.com





5.TRACEABILITY DETAILS OF INSTRUMENTS USED FOR TESTING					
S.no	Name of the instrument	Make	Model	Serial no	Cal Due
1.	Electrical safety analyser	Fluke	Esa612	3005050	07-OCT-2023

S.NO	PARAMETER	OBSERVED VALUE	ACCEPTANCE LIMITS AS PER THE STD	REMARKS
1.	Protective earth resistance	0.129Ω	< <b>0.3</b> Ω	Ok
2.	Earth leakage	134.21µA	<210 µA NC	Ok
3.	Patient leakage current	NA	<100 µA BF	Ok
4.	Equipment current	0.3A	As per the manufacture spec	Ok
5.	Mains voltage (P-E)	230.5V		Ok
6.	Mains voltage (P-N)	231.2V		Ok
7.	Mains voltage (N-E)	1.0V	<5V	Ok
8.	Enclosure leakage current	50 µA	<100 µA (normal)	Ok
9.	Insulation resistance	OL	>100 M Q	Ok

S.NO	7.Remarks
1.	This report is applicable to the sample tested only
2.	The instrument used for testing are valid calibration and are traceable to national standards
3.	Parameter of the DUT were verified and found to be within the specified limits

## Verified by :

<b>Q</b>	(c)	$\bowtie$	
No. 42/1, Navaindia Road,Peelamedu,	99400 28355, 97512 06106	hbmedicalsystem@gmail.com	

Coimbatore-641 004.

hbmssales@gmail.com