



Trust & Care



CALIBRATION REPORT	
Report No : HBMS/CAL/23-24	Calibration Date : 23.08.2023
	Calibration Valid: 22.02.2024
<b>1.1.CUSTOMER DETAILS:</b>	
Name and Address of the organization	M/s, PRIMARY HEALTH CENTRE, POOLAMPATTI,SALEM.
<b>1.2. DESCRIPTION OF DEVICE UNDER TEST (DUT):</b>	
EQUIPMENT NAME	CENTRIFUGE
i	Manufactured by BDI
ii	Model BDI-152
iii	Serial No PHC/CF/PP/001

**CALIBRATION WORKSHEET**

LOCATION: LABORATORY

**Tabulation For – Centrifuge**

S.no	Unit under test IN Minutes	Observed speed tachometer in RPM	Deviation measured ± RPM	Combined uncertainty in RPM in % rdg
1	1000	1000	2	1.12
2	1200	1201	2	1.23
3	1500	1502	4	1.56
4	2000	1999	1	1.175

Acceptable deviation is ± 5 RPM it depends on Max Speed Range

MD Reg No: TN/CBE/MD42/00016

GSTIN: 33AAJFH1833M1ZB

99400 28355, 9751206106

88833 15662

No.42/1, Navaindia Road, Peelamedu,

CBE – 04, hbmedicalsystem@gmail.com

### 5. TRACEABILITY DETAILS OF INSTRUMENTS USED FOR TESTING

S.No	Name of the instrument	Make	Model	Serial no	Cal Due
1.	Electrical safety analyser	Fluke	Esa612	3005050	07 OCT 2023

### 6. ELECTRICAL SAFETY TEST

S.NO	PARAMETER	OBSERVED VALUE	ACCEPTANCE LIMITS AS PER THE STD	REMARKS
1.	Protective earth resistance	0.129Ω	<0.3 Ω	Ok
2.	Earth leakage	134.21μA	<210 μA NC	Ok
3.	Patient leakage current	NA	<100 μA BF	Ok
4.	Equipment current	0.3A	As per the manufacture spec	Ok
5.	Mains voltage (P-E)	230.5V	--	Ok
6.	Mains voltage (P-N)	231.2V	--	Ok
7.	Mains voltage (N-E)	1.0V	<5V	Ok
8.	Enclosure leakage current	50 μA	<100 μA (normal)	Ok
9.	Insulation resistance	OL	>100 M Ω	Ok

S.NO	7.Remarks
1.	This report is applicable to the sample tested only
2.	The instrument used for testing are valid calibration and are traceable to national standards
3.	Parameter of the DUT were verified and found to be within the specified limits

Verified by :



MD Reg No: TN/CBE/MD42/00016

GSTIN: 33AAJFH1833M1ZB

99400 28355, 9751206106

88833 15662

No.42/1, Navaindia Road, Peelamedu,  
CBE – 04, hbmedicalsystem@gmail.com